BRUHAT BANGALORE MAHANAGARA PALIKE

3BMP/2016-17/RD/WORK_INDENT24281/CALL-:

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/20/2016-17, Date: 12.01.2017

Improvements to roads and drains in amruthahalli gramathana in ward no.07, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B.R. Dhananjaya	
				In Figures	In Words
1	354.65	KSRB 2-2.2:Earth work excavation for foundation of building, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ORDINARY soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches , stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications and direction of the Engineer-in-charge.	Cum	77.96	Rupees Seventy Seven and Ninety Six Paise Only
2	84.53	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification .	Cum	4753.69	Rupees Four Thousand Seven Hundred Fifty Three and Sixty Nine Paise Only
3	24.14	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications.	Cum	5147.55	Rupees Five Thousand One Hundred Forty Seven and Fifty Five Paise Only
4	80.48	KSRB 4.2.2: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastizers @ 3lts confirming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts butresses string or lacing courses parapets copings, bed blocks , plain windows cills fillets etc., including cost of all materials labour HOM of machinery curing complete as per specifications.	CUM	5810.74	Rupees Five Thousand Eight Hundred Ten and Seventy Four Paise Only
5	5.23	KSRB 4-.9-2:Providing and fabricating TMT . Steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking,placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design(laps and wasteage shall not measured and paid) cost of materials. labour. HOM of machinery complete as per specifications . (Page NO 17, Itm. NO. 4.46.2)	tonne	55619.92	Rupees Fifty Five Thousand Six Hundred Nineteen and Ninety Two Paise Only
6	789.6	KSRB 4-6.4: Providing and removing centering, shuttering strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness including attached pilasters, buttressed, plinth and string courses cost of all materials, labour complete as per specifications	Sqm	287.55	Rupees Two Hundred Eighty Seven and Fifty Five Paise Only
7	60.3	KSRB 4-48: Providing and laying in cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for RCC works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complate (exclusive of cost of steel and fabrication charges	Cum	5936.29	Rupees Five Thousand Nine Hundred Thirty Six and Twenty Nine Paise Only
8	3.24	KSRB 5.3-1:Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms hign, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications.	Cum	3240.0	Rupees Three Thousand Two Hundred Forty Only
9	36	KSRB 5.3-1:Providing ruled pointing of course stone msonry with cement mortar 1:3 20 mm deep, after raking joints to depth of 20 mm nicley lining, including cost of materials, labour, curing etc., complete as per specifications and directions of the engineer-in-charge.	Sqm	33.41	Rupees Thirty Three and Forty One Paise Only

Signature of the contractor

Executive Engineer

05/04

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B.R. Dhananjaya	
				In Figures	In Words
10	200.4	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications	Sqm	1721.25	Rupees One Thousand Seven Hundred Twenty One and Twenty Five Paise Only
11	6.48	Providing and fixing 20 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing comlete as per specification	Cum	4791.56	Rupees Four Thousand Seven Hundred Ninety One and Fifty Six Paise Only
12	350	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification	Cum	88.89	Rupees Eighty Eight and Eighty Nine Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

05/04